



ASOS 2.0 - An Update

NWS Automated Surface Observations (ASOS) 2.0

- The Acquisition Control Unit (ACU), Data Collection Package(DCP), Single Cabinet ASOS (SCA) Upgrade Project
 - Will allow for ASOS sensor instrumentation and communications modernization initiatives
 - Integrated system built by Campbell Scientific Inc. (CSI)
 - Includes new hardware and software that allows for an upgrade to modern IP communications, sensor/system integration and expanding the availability and periodicity of ASOS data



ASOS 2.0 - An Update

NWS Automated Surface Observations (ASOS) 2.0

- Timeline:
 - CY2024: Complete upgrade of Ice Free Wind Sensor, Complete Temperature/Dew Point Sensor replacement, Begin transmitting ceilometer attenuated backscatter data sets for operational use
 - CY2026: Design, validate and deploy all ACU/DCP/SCA Replacements (aka ASOS 2.0), Replace all copper voice and data lines with Internet Protocol communications, Deploy new ceilometer, Deploy new precipitation weighing gauge, Deploy new barometer
 - CY2027: Deploy new visibility and present weather sensor combination unit, Achieve GCOS1 Surface Reference Network Instrumentation standards for wind and temperature
 - CY2028: Achieve GCOS Standards at NWS ASOS 2.0 sites for Solar Radiation, Deploy new freezing rain sensor
 - CY2029: Deploy new tipping bucket sensor



COOP 2.0 - An Update

- **NWS Cooperative Observer Program (COOP)**
- Major update to the Station Information System (SIS)
 - Internal program used for documentation of COOP station and observer information
- Closer to home: If funding comes through, the Central Region of the NWS will update Cellular COOP(C-COOP) technology
- **NWS COOP Going Forward...**